2011 HIGHLAND PARK MOBILE HOMES Park Model Comparison Sheet Features and Engineering

Highland Park Mobile Homes	Product "A"	Product "B"	Product "C"
			,
Engineered & Oversized			
12" Steel I beam frame			
			Π
Engineered 12" open web transverse			
floor system with integrated duct			
runners permitting true perimeter			
heating for added comfort			
R-40 cellulose insulation in floor STD			
R-40 cellulose insulation in ceiling			
2" x 6" walls with R-23 insulation			
(16" centre & 90" high)			
Engineered roof truss design by far			
exceeding snow load requirements			
for Northern Ontario !			
7/16" exterior wood sheathing			
on all walls			
Tyvek exterior wrap over sheathing			
Tuck taped to housing code specs.			
Canadian made vinyl siding			

Highland Park Mobile Homes	Product "A"	Product "B"	Product "C"
----------------------------	-------------	-------------	-------------

Stronger "Super 6" Housing Code		
vapour barrier with acoustic sealant		
applied to all seams		
(like an R-2000 home!)		
(all codes exceeded)		

Wood sheathed underbelly		
Spray sealed and "rodent proof"		

25 yr. shingle on roof STD		
35 yr. fiberglass opt. (approx. \$350.)		

Tar paper underlay on entire roof		
with ice and water shield along		
lower 3' of roof line.		
(all codes exceeded)		

Double hung vinyl thermopane		
windows STD (Grills Opt.)		
All window jambs double framed and		
spray foam sealed (all codes exceeded!)		

Spray textured "California Style"		
drywalled vaulted ceiling throughout		

Sound deadening 1/2" vinyl covered		
drywall with various colours to		
choose from (not panelling)		

Decora style residential quality wall		
switches & receptacles throughout		
(not the "RV" style switch/box		
combo units that regularly fail)		

Highland Park Mobile Homes Pro	duct "A" Product "B"	Product "C"
--------------------------------	----------------------	-------------

I-	I	
Full thickness residential grade		
formica counter tops with many		
colours to choose from		
(backsplash std)		
Solid oak framed cabinet		
doors (raised panel optional).		
Cabinet structures are made from		
residential quality melamine (not		
paper over pressboard or panelling)		
and are installed in models as in		
premium built homes.		
(not stick built on the spot with		
1" x 1" strapping)		
Deluxe residential european hidden		
hinges std. on all cabinet doors		
(latest edition "soft close" available)		
П	II	
All drawer fronts are solid oak with		
heavy duty melamine frames and		
come with smooth roll glides		
Residential style deluxe colonial		
moulding used throughout (includes		
ceiling, base board, all window and		
door jambs)	<u> </u>	
All interior doors are white painted		
series "800" full residential quality		
including hinges and lever hardware		
(brass or pewter)		
Electric 5/0" tengue and gracite		
Floor is 5/8" tongue and groove		
plywood glued and screwed		
(all codes exceeded)		

II' alchend Derde Maleile Herree	Dreader at "A"	Deve des st "D"	Dreader at "C"
Highland Park Mobile Homes	Product A	Product "B"	Product "C"

1/4" Mahogany sheathing placed		
over plywood floors where vinyl is to		
be installed (smoother floor just as		
done in premium homes)		
	<u>н</u>	
Deluxe 35oz carpet STD (40oz opt.)		
heavy duty scuff resistant vinyl		
flooring STD in kitchen, bath & hall		
	I II	n
Premium 32" insulated rear entrance		
door with thermopane window and		
grills. 2" thick self storing		
storm door available. (not the R.V.		
style that looks residential)		
Heavy duty 6' vinyl insulated		
thermopane patio door STD		
("low E" glass opt.) (grills opt.)		
Deluxe 56,000 BTU gas furnace		
with auto ignition and 2 speed		
blower fan STD		

C.S.A. Z240 code available- our standard unit exceeds this code

Ontario Building code - Yes!! - Our building guideline... and quite often exceeded!

CHECK US OUT!!!

Highland Park - "YOUR Project Partners"

Phone # 1 - 519 - 475 - 4471 Fax # 1 - 519 - 475 - 4155 e-mail john@happyhills.com